



Request for Quotation

RFQ No.1129

Supplier's Names

Supplier Contact email

Supplier Contact Telephone Number

Date of RFQ

Date of RFQ Return

17/9/2025

22/9/2025

S/No	Item	Descriptions	Quantity	UOM	Unit Price	Total Amount	Packaging unit
1	Storage facility/Small office construction in two local	Juba (Nyaiag) and (Rejaif tokimang east)		2 stores			
2	Main Store measurement 15,600mm * 7,600mm	600mm*200mm thick strong foundation laid on soil stratum with 800mm*200mm thick strip foundation laid on soil stratum with adequate withstanding strength of transmitted foundation hands. 36mm thick cement screed on 150mm concrete slab placed on DPM on to 200mm hard core on well compacted marrum and well treated and approved anti-termite treatment on 50mm thick concrete building of mix (1:3:6) cement/sand/Aggregates/20mm. Roofing: 25deg. roof pitch pre-patted iron angle ridge on pre-					
3	Main Store measurement 15,600mm * 7,600mm (Tokimman East)	600mm*200mm thick strip foundation laid on soil stratum with adequate withstanding strength of transmitted foundation hands. 36mm thick cement screed on 150mm concrete slab placed on DPM on to 200mm hard core on well compacted marrum and well treated and approved anti-termite treatment on 50mm thick concrete building of mix (1:3:6) cement/sand/Aggregates/20mm. Roofing: 25deg. roof pitch pre-patted iron angle ridge on pre-					
4	Small store measurement 10,400mm*4,400mm (Nyaiag)	600mm*200mm thick strip foundation laid on soil stratum with adequate withstanding strength of transmitted foundation hands. 36mm thick cement screed on 150mm concrete slab placed on DPM on to 200mm hard core on well compacted marrum and well treated and approved anti-termite treatment on 50mm thick concrete building of mix (1:3:6) cement/sand/Aggregates/20mm. Roofing: 25deg. roof pitch pre-patted iron angle ridge on pre-patted iron roofing sheets nailed on to 100*50mm purlins on 100*50mm rafters with 100*50mm struts and ties on 150*50mm tie beam resting on 100*75mm wall plates. Ceiling: Metal lathe plastered ceiling fixed on to 100*50mm ceiling joints and 50*50mm branderings					
5							
6							
7							
8							
9							
Total							

Quotation Validity
Terms of Payments
Delivery Period

WFC

Approved by:

Signature

Date

Stamp

for
17/09/2025

Supplier Rep:
Names

Signature

Date

Stamp

